



- NOTES:
- FOR LEGEND AND SYMBOLS SEE DRAWINGS P-D-00-10,11,12 & 13
 - DELETED.
 - OVERHEAD PRESSURE TAP TO BE AT SAME OR LOWER ELEVATION AS CENTER TAP AND TO BE ACCESSIBLE AT PLATFORM
 - DELETED.
 - TOP CONNECTION.
 - DELETED.
 - SYMMETRICAL PIPING
 - TOWER A-380R MUST BE ELEVATED ABOVE THE PIPERACK TO PREVENT FLASHING WITH GRAVITY FLOW TO T-389AR
 - LOCATE G-380R AT LOW POINT NEAR A-380R
 - TRIP (XV-3002) WHEN R-300R COMPRESSOR SHUTDOWN.
 - DELETED.
 - DELETED.
 - DELETED.
 - DELETED.
 - NEW EQUIPMENT TO REPLACE EXISTING EQUIPMENT AND TO BE INSTALLED AT NEW LOCATION.
 - NEW EXCHANGER T-379R REPLACES EXISTING T-379 AT NEW LOCATION.
 - EXCHANGER T-380AR/BR CENTERLINE SHALL BE AT THE SAME ELEVATION AS A-380R BTL.
 - TOP MOUNTED, FREE DRAINING.
 - LOW POINT DRAIN.
 - LINE SHALL NOT RISE ABOVE A-380R BTL.
 - TWO PHASE FLOW. ANCHOR SECURELY.
 - REBOILER RETURN NOZZLES AT THE SAME ELEVATION.
 - DELETED.
 - DELETED.
 - DELETED.
 - DELETED.
 - PT
 - GEAR TYPE HANDWHEEL.

1	2019 NOV.29	ISSUE FOR CONSTRUCTION-1	M.J.O	S.J.K	P.H.C	N.H.H
0	2019 SEP.18	ISSUE FOR CONSTRUCTION	M.J.O	S.J.K	P.H.C	N.H.H
2	2020 MAR.31	ISSUE FOR CONSTRUCTION-2	M.J.O	S.J.K	P.H.C	N.H.H
1A	2020 FEB.14	ISSUE FOR CONSTRUCTION-2	M.J.O	S.J.K	P.H.C	N.H.H
25	2017 FEB.24	REVISED AS PER W/O 메틸2-200410405 김민수 박갑기 김승준 주철규 노대영				
REV.	DATE	REVISION DESCRIPTION	DWN.	CHK'D	CHK'D	PM
CERT.FOR CONST.	DATE					
RESP.ENG.	DRAWN BY	DATE	CHECKED BY	DATE		
YNUCC YEOCHUN NCC Co.,Ltd.						
YNUCC NCC2 REVAMP PROJECT						
Hanwha Engineering&Construction						
TITLE						
PIPING & INSTRUMENT DIAGRAM HP DEPROPANIZER						
TechnipFMC						
J.O. NUMBER	DRAWING NUMBER		REV.NO.			
I-2018-159	P-D-03-19		2			